

COUNTY GOVERNMENT OF KIRINYAGA



**DEPARTMENT OF FINANCE AND ECONOMIC PLANNING
OFFICE OF THE DIRECTOR SUPPLY CHAIN MANAGEMENT**

Telephone: +254-020-8010181
Email: procurement@kirinyaga.go.ke
When replying please quote;

**KIRINYAGA COUNTY GOVERNMENT
P.O.BOX, 260
KUTUS.**

ADDENDUM NO. 20

29th MARCH, 2021

TO ALL PROSPECTIVE BIDDERS

RE: RE-TENDER FOR SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF AUTOMATIC YOGHURT PRODUCTION UNIT WITH A CAPACITY OF 200LTRS.

The County Government of Kirinyaga has issued the following addendum with regards to the following tender;

S/No	TENDER DESCRIPTION	CLARIFICATIONS
1.	CHANGE OF TENDER DESCRIPTION CGK/SCM/ALV&F/012/20 20-2021 RE-TENDER FOR SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF AUTOMATIC YOGHURT	The tender description of the mentioned Supply, Delivery and Installation change from RE-TENDER FOR SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF AUTOMATIC YOGHURT PRODUCTION UNIT WITH A CAPACITY OF 200LTRS to RE-TENDER FOR SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF 3 SEMI-AUTOMATIC YOGHURT PRODUCTION UNIT WITH A CAPACITY OF 200LTRS (DAIRY VALUE CHAIN)

	PRODUCTION UNIT WITH A CAPACITY OF 200LTRS.					
2.	SCHEDULE OF REQUIREMENT AND PRICE SCHEDULE TENDER NO: CGK/SCM/ALV&F/012/2020-2021 RE-TENDER FOR SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF 3 SEMI-AUTOMATIC YOGHURT PRODUCTION UNIT WITH A CAPACITY OF 200LTRS (DAIRY VALUE CHAIN)	Kindly note the following amended areas on the Schedule of Requirements and Price Schedule. SECTION VI - SCHEDULE OF REQUIREMENTS NAME OF TENDER: SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING 3 SEMI-AUTOMATIC YOGHURT PRODUCTION UNIT WITH A CAPACITY OF 200LTRS FOR KIRIMA, RUKINGO AND RUNGETO (DAIRY VALUE CHAIN) TENDER NO: CGK/SCM/ALV&F/012/2020-2021				
S/N	Unit	Description	Specifications	Quantity	Estimate Cost	DELIVERY TIMELINESS
1.	Milk Reception Unit	Dump Tank	- Capacity: 200 Litres. - Made in stainless steel. Square shape with round corners. - With large outlet and butterfly valve connected to the pump	3		
		Food Hose Pipe	- Food grade quality wire braided - Diameter of 25mm supplied in 5 meter lengths	3		
		Milk weighing scale plus vat	- Made in stainless steel; Up to 200Kgs. - Platform 600mm x 600mm - With adjustable legs	3		

			Milk pump	- Centrifugal, up to 3m³/hr - Motor: 0.75kWatt - Parts in contact with the product in stainless steel AISI 316 - Stainless steel shroud and base with adjustable legs	3		
2.	Pasteurizer/ inoculator	Batch Pasteurizer	500L Capacity - Stainless steel AISI 304 with insulated double walls. - Electrical heating Element - Agitator motor mounted on the cover. - Electronic control panel - Water pump for the circulation of heating and cooling water. - Outlet valve at the bottom	3			
3.	Chilling Unit	Ice Water Accumulator	- Energy capacity; 25,000k Cal - Capacity Tank; 500L - Thick stainless steel AISI 304 - Outer and inner vessel with environmental friendly polyurethane foam - Evaporator is made of seamless copper tubes and mounted in a stainless steel frame - Ice water pump - Ice thickness sensor - An air blower - Electrical switch board	3			

4.	Packaging unit	Semi-automatic yoghurt cup sealer	• Complete stainless steel machine with acrylic doors and safety locks • 6 working positions. With hopper and heat seal unit • Cup loader and feeder with vacuum device • Piston filler for viscous dairy products with range 100-500gms • Capacity: +/- 600 cups per hour • Washing spray ball for product hopper • Self-diagnostics system • Lid sealing device • Inkjet printer for date coding • Electric panel with touch screen panel	3		
	Labour	Delivery Installation & Commissioning	To the site Installation	3		
				3		

SECTION VII - PRICE SCHEDULE

NAME OF TENDER: SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF 3 SEMI-AUTOMATIC YOGHURT PRODUCTION UNIT WITH A CAPACITY OF 200LTRS FOR KIRIMA, RUKINGO AND RUNGETO (DAIRY VALUE CHAIN)

TENDER NO: CGK/SCM/ALV&F/012/2020-2021

S/N	Unit	Description	Specifications	Quantity	Estimate Unit Cost	Total Cost
1.	Milk Reception Unit	Dump Tank	• Capacity: 200 Litres. • Made in stainless steel. Square shape with round corners. • With large outlet and butterfly valve connected to the pump	3		

3.	Chilling Unit	Ice Water Accumulator	• Energy capacity; 25,000k Cal • Capacity Tank; 500L • Thick stainless steel AISI 304 • Outer and inner vessel with environmental friendly polyurethane foam • Evaporator is made of seamless copper tubes and mounted in a stainless steel frame • Ice water pump • Ice thickness sensor • An air blower • Electrical switch board	3		
	4.	Packaging unit	Semi-automatic yoghurt cup sealer	• Complete stainless steel machine with acrylic doors and safety locks • 6 working positions. With hopper and heat seal unit • Cup loader and feeder with vacuum device • Piston filler for viscous dairy products with range 100-500gms • Capacity: +/- 600 cups per hour • Washing spray ball for product hopper • Self-diagnostics system • Lid sealing device • Inkjet printer for date coding • Electric panel with touch screen panel	3	
		Labour	Delivery Installation & Commissioning	To the site Installation	3	
					3	
						TOTALS FOR 3

3.	CHANGE OF SUBMISSION DATE.	The tender submission date for the mentioned Supply, Delivery and Installation is hereby extended from Wednesday 31st March, 2021 at 2.00 P.M to or before Tuesday 6th April, 2021 at 2.00 P.M. East Africa Time.
----	---------------------------------------	--



DIRECTOR SUPPLY CHAIN MANAGEMENT SERVICES
FOR: COUNTY SECRETARY