REPUBLIC OF KENYA

COUNTY GOVERNMENT OF KIRINYAGA

DEPARTMENT OF FINANCE AND ECONOMIC PLANNING
OFFICE OF THE DIRECTOR SUPPLY CHAIN MANAGEMENT

Telephone:
Email: procurement@kirinyaga.go.ke.

KIRINYAGA COUNTY GOVERNMENT
P.O.BOX, 260 - 10304
KUTUS.

When replying please quote.

Ref. No.CGK/SCM/ADD/ONT/Vol. 1(001)

03rd October, 2023

TO ALL PROSPECTIVE BIDDERS

RE: ADDENDUM NO.1 - TENDER FOR THE INSTALLATION OF CULVERT LINES IN VARIOUS SPOTS WITHIN VARIOUS WARDS IN MWEA SUB-COUNTY - KIRINYAGA COUNTY - CGK/TR&I/ONT/007/2023-2024

Reference is made to the Tender Notice of 27th September, 2023 inviting interested, eligible and qualified bidders to bid for Road works contracts for Financial Year 2023-2024.

Pursuant to section 75 of the Public Procurement and Asset Disposal Act, 2015, its attendant Regulations 2020, the County Government of Kirinyaga has issued the following addendum with regards to the above mentioned tender.

S/NO	TENDER NUMBER	TENDER NAME	IFMIS NO.	CORRECTION.
1.	CGK/TR&I/ ONT/007/2 023-2024	**CHANGE OF THE BILL OF QUANTITY:** Tender for the Installation of Culvert Lines in various spots within various Wards in Mwea Sub-County - Kirinyaga County	**1356995-2023/2024**	*The Bill of Quantity on page 60 - 66 has been amended as attached*

COUNTY GOVERNMENT OF KIRINYAGA
DIRECTOR SUPPLY CHAIN MANAGEMENT
Sign:.....
Date:.....
P.O. Box 260 - 10304 KUTUS

KEVIN MUTINDA
DIRECTOR SUPPLY CHAIN MANAGEMENT

Tenderers are advised that the Bill of Quantity on page 60 – 66 of the Tender document has been amended as attached below.

Project name:	**Construction of Kirundo Bridge in Kangai ward**				
Road No.:	**Unclassified**				
No of Structures	**2**			**Span = 6.0x3.0x2.0m**	
Bill of Quantities					Page: 1
Bill No.1	**General: Office administration and overheads/Preliminaries**				**Project:**
Item No.	**Description**	**Units**	**Quantity**	**Unit Bid Rate(Ksh)**	**Amount KSh**
1.01	Provide and erect Bill Boards	No.	1.00		
1.02	Allowances for Technical Contract supervision, Quality control and Materials testing as directed by the Engineer	Lump Sum	500,000.00	1.00	500,000.00
1.03	As item 1.02 but for Contractor's Overheads & Profits	%			
	Total Carried Forward to Summary:				
Road name:	**Construction of Kirundo Bridge in Kangai ward**				
Road No.:	**Unclassified**				
No of Structures	**2**			**Span = 6.0x3.0x2.0m**	
Bill of Quantities					Page: 2
Bill No.7	**EXCAVATION & FILLING FOR STRUCTURES.**				**Project:**
Item No.	**Description**	**Units**	**Quantity**	**Unit Bid Rate(Ksh)**	**Amount KShs**

7.01	Excavate in soft material to any depth for bridge foundation and spoil the excavated materials including river diversion as directed by the Engineer.	M^3	150		
7.02	Excavate in hard material to any depth for bridge foundation and spoil the excavated materials including river diversion as directed by the Engineer.	M^3	15		
7.03	Provide and deposit rock fill for the foundations, compact 100% MDD (AASHTO T99)	M^3	30		
7.04	Provide and deposit graded granular material backfill around abutments, including gravel materials for the approaches on both sides and compact 100% MDD (AASHTO T99)	M^3	30		
	Total Carried Forward to Summary:				
Road Name:	**Construction of Kirundo Bridge in Kangai ward**				
Road No.:	**Unclassified**				
No of Structures	**2**			**Span = 6.0x3.0x2.0m**	
Bill of Quantities					Page: 3
Bill No.17	**CONCRETE WORKS**				**Project:**
Item No.	**Description**	**Units**	**Quantity**	**Unit Bid Rate(Ksh)**	**Amount KShs**
	BLINDING LAYER	-			
	Provide, place and compact the following classes of concrete as speficied				
17.01	Class 15/20 concrete	M^3	3.00		

	CONCRETE WORKS	-			
	Provide, place and compact the following classes of concrete as speficied				
17.02	Class 25/20 concrete	M^3	35.00		
	FORMWORK				
	Provide, erect and afterwards dismantle and remove all the formwork as specified by the Engineer				
17.03	Formwork Class F2 Finish (Smooth)	M^2	120.00		
	REINFORCEMENT				
	Provide, bend and fix into positions High Yield and Mild Steel bars to BS4461 the following steel reinforcement as directed				
17.04	Reinforcement bars of High Yield strength to BS 4461, size 10mm	Kgs	600		
17.05	Reinforcement bars of High Yield strength to BS 4461, size 12mm	Kgs	1,350		
17.06	Reinforcement bars of High Yield strength to BS 4461, size 16mm	Kgs	400		
17.07	Reinforcement bars of High Yield strength to BS 4461, size 20mm	Kgs	400		
	Total Carried Forward to Summary:				
Road name:	**Construction of Kirundo Bridge in Kangai ward**				
Road No.:	**Unclassified**				
No of Structures	**2**			**Span = 6.0x3.0x2.0m**	
Bill of Quantities					Page: 4
Bill No.20	**ROAD FURNITURE**				**Project:**

Item No.	Description	Units	Quantity	Unit Bid Rate(Ksh)	Amount KShs
20.01	Provide and place new Galvanized steel pipe 75mm diameter hardrails and fix them 100mm from the top of the guardrail posts as directed by the Engineer.	M	12		
20.02	Provide and cast 1200x300x300mm guardrail posts in concrete class 25(20) reinforced with Y16 square twisted steel as shown on the drawings or as directed by the Engineer.	No	6		
20.03	Provide and place metallic, galvanized flexural W-beams Guardrails including their posts as directed by the Engineer.	M	24		
	Total Carried Forward to Summary:				

Road name:	**Construction of Kirundo Bridge in Kangai ward**	
Road No.:	**Unclassified**	
No of Structures	**2**	**Span = 6.0x3.0x2.0m**
Bill of Quantities		Page: 5
	Summary	**Project:**
Item No.	**Description**	**Amount (KShs)**
1	General: Office administration and overheads/Preliminaries	
7	EXCAVATION & FILLING FOR STRUCTURES.	
17	CONCRETE WORKS	
20	ROAD FURNITURE	
	Sub Total 1	
	Allow for 16% for Value Added Tax (V.A.T)	

	Total carried to the summary				
Project Name:	**Installation of Culvert Lines at Rurii South, Kianganga and Kiorugari areas within Nyangati ward**				
	Contract No. :----------				**5No Lines**
Bill of Quantities					Page: 1
	Bill No.1: Preliminaries & General Items				**Project:**
Item No.	**Description**	**Units**	**Quantity**	**Unit Bid Rate(Kshs)**	**Amount KShs.**
1.01	Provide prime cost sum (PC sum) of Kshs. 100,000 for RE's transport, allowances and work control and other miscellaneous expenditure.	PC Sum	100,000.00	1	100,000.00
1.02	As item 1.01 but for Contractor's Overheads & Profits	%			
	Total Carried Forward to Summary:				
Project Name:	**Installation of Culvert Lines at Rurii South, Kianganga and Kiorugari areas within Nyangati ward**				
	Contract No. :----------				**5No Lines**
Bill of Quantities					Page: 2
	Bill No.8: CULVERT AND DRAINAGE WORKS				
Item No.	**Description**	**Units**	**Quantity**	**Unit Bid Rate (Kshs)**	**Amount KShs**
8.01	Excavate for culverts of any diameter as instructed by the Engineer	M^3	40.0		
8.02	Provide, install, joint 600 dia. Culverts with 1:2 cement sand mortor	M	30.0		

8.03	Provide and place Class 20/20 concrete for culvert blinding and surround	M^3	19.50		
8.04	Provide and place Class 20/20 concrete to Aprons, Headwalls and Wing walls.	M^3	7.50		
8.05	Provide, fix and dismantle after use the following formwork for the culverts	M^2	75.00		
8.06	Provide and spread selected backfill material to the culverts incluiding approaches.	M^3	5.0		
	Total Carried Forward to Summary:				

Project Name:	**Installation of Culvert Lines at Rurii South, Kianganga and Kiorugari areas within Nyangati ward**	
	Contract No. :----------	**5No Lines**
Bill of Quantities		Page: 3
	SUMMARY	
Item No.	**Description**	**Amount (KShs)**
1	Bill No.1: Preliminaries & General Items	
8	CULVERT AND DRAINAGE WORKS	
	Sub Total 1	
	Add 16% VAT of Sub Total 1	
	Total carried to the Summary	

Project Name:	**Installation of Culvert Lines at various spots within Thiba ward**				
	Contract No. :----------				**5No Lines**
Bill of Quantities					Page: 1

	Bill No.1: Preliminaries & General Items				Project:
Item No.	**Description**	**Units**	**Quantity**	**Unit Bid Rate(Kshs)**	**Amount KShs.**
1.01	Provide prime cost sum (PC sum) of Kshs. 100,000 for RE's transport, allowances and work control and other miscellaneous expenditure.	PC Sum	100,000.00	1	100,000.00
1.02	As item 1.01 but for Contractor's Overheads & Profits	%			
	Total Carried Forward to Summary:				**100,000.00**

Project Name:	**Installation of Culvert Lines at various spots within Thiba ward**				
	Contract No. :----------				**5No Lines**
Bill of Quantities					Page: 2
	Bill No.8: CULVERT AND DRAINAGE WORKS				
Item No.	**Description**	**Units**	**Quantity**	**Unit Bid Rate (Kshs)**	**Amount KShs**
8.01	Excavate for culverts of any diameter as instructed by the Engineer	M^3	40.0		
8.02	Provide, install, joint 600 dia. Culverts with 1:2 cement sand mortor	M	30.0		
8.03	Provide and place Class 20/20 concrete for culvert blinding and surround	M^3	19.50		
8.04	Provide and place Class 20/20 concrete to Aprons, Headwalls and Wing walls.	M^3	7.50		
8.05	Provide, fix and dismantle after use the	M^2	75.00		

	smooth formwork for the culverts				
8.06	Provide and spread selected backfill material to the culverts incluiding approaches.	M^3	5.0		
	Total Carried Forward to Summary:				

Project Name:	**Installation of Culvert Lines at various spots within Thiba ward**	
	Contract No. :----------	**5No Lines**
Bill of Quantities		Page: 3
	SUMMARY	
Item No.	**Description**	**Amount (KShs)**
1	Bill No.1: Preliminaries & General Items	
8	CULVERT AND DRAINAGE WORKS	
	Sub Total 1	
	Add 16% VAT of Sub Total 1	
	Total carried to the Summary	

Project Name:	**Installation of Culvert Lines at various spots within Murinduko ward**				
	Contract No. :----------				**6No Lines**
Bill of Quantities					Page: 1
	Bill No.1: Preliminaries & General Items				**Project:**
Item No.	**Description**	**Units**	**Quantity**	**Unit Bid Rate(Kshs)**	**Amount KShs.**

1.01	Provide prime cost sum (PC sum) of Kshs. 160,000 for RE's transport, allowances and work control and other miscellaneous expenditure.	PC Sum	150,000.00	1	150,000.00
1.02	As item 1.01 but for Contractor's Overheads & Profits	%			
	Total Carried Forward to Summary:				
Project Name:	**Installation of Culvert Lines at various spots within Murinduko ward**				
	Contract No. :----------				**6No Lines**
Bill of Quantities					Page: 2
	Bill No.8: CULVERT AND DRAINAGE WORKS				
Item No.	**Description**	**Units**	**Quantity**	**Unit Bid Rate (Kshs)**	**Amount KShs**
8.01	Excavate for culverts of any diameter as instructed by the Engineer	M^3	45.0		
8.02	Provide, install, joint 600 dia. Culverts with 1:2 cement sand mortor	M	36.0		
8.03	Provide and place Class 20/20 concrete for culvert blinding and surround	M^3	23.50		
8.04	Provide and place Class 20/20 concrete to Aprons, Headwalls and Wing walls.	M^3	9.00		
8.05	Provide, fix and dismantle after use the following formwork for the culverts	M^2	90.00		
8.06	Provide and spread selected backfill material to the culverts incluiding approaches.	M^3	350.0		

	Total Carried Forward to Summary:				
Project Name:	**Installation of Culvert Lines at various spots within Murinduko ward**				
	Contract No. :----------				**6No Lines**
Bill of Quantities					Page: 3
	SUMMARY				
Item No.	**Description**				**Amount (KShs)**
1	Bill No.1: Preliminaries & General Items				
8	CULVERT AND DRAINAGE WORKS				
	Sub Total 1				
	Add 16% VAT of Sub Total 1				
	Total carried to the form of Tender				

SUMMARY	
Construction of Kirundo Bridge in Kangai ward	
Installation of Culvert Lines at various spots within Murinduko ward	
Installation of Culvert Lines at Rurii South, Kianganga and Kiorugari areas within Nyangati ward	
Installation of Culvert Lines at various spots within Thiba ward	
Total carried to the Form of Tender	

CONTRACTOR

NAME.....

SIGNATURE.....

ADDRESS.....

DATE & STAMP.....

WITNESS

NAME.....

SIGNATURE.....

ADDRESS.....

DATE & STAMP.....